

# BURJ KHALIFA – CONSTRUCTION AND QUALITY CONTROL

D.S. Rajendra Prasad<sup>1</sup>

<sup>1</sup>Sr. QA/QC Projects Manager, Azmeel Contracting Company, Kingdom of Saudi Arabia

## Abstract

This paper presents a snapshot of Construction and Quality Control system adopted during the construction of World's Tallest Tower, "The BurjKhalifa Tower", Dubai, UAE. An effective, well-constructed and well-maintained building is essential for safety and durability of any structure. In order to achieve this, the safety and quality aspects should be built-in during the design and construction stage rather than at the inspection stage. The construction practices adopted at BurjKalifa Tower is simply "Do the right thing, right, first time, every time" by following established approved Project Quality Plan (PQP) and Inspection Test Plans (ITPs) with well narrated method statements and definite objective checklists/formats. Project Management Information System (PMIS) was effectively and efficiently used in day-to-day construction activities for ensuring: an advanced information on construction activity (what, when, where, who, how, with what), with well repository of documents, good track on resources, providing precise information to subcontractors and keep a tab on commercials. DOKA Auto-climbing formwork was used for the Tower cores and HunnebeckTable formwork for the Podium slabs and FRP shuttering for walls of circular Car parking ramps. Aluminum shuttering (MevaDec panel formwork) was adopted for tower slabs. C80 grade concrete was used in tower columns and shear walls and C50 grade concrete for beams and slabs. Podium rafts was casted with C50 grade concrete. Tower walls constructed adopting 3-day cycle for each level and reinforcement bars were fabricated for the height of 2 levels with couplers for the laps for beams and slabs and for nose columns. De-shuttering of tower walls after 10hours of pull-out tests complying with a minimum strength of 10MPa. Composite link beams were used to connect core walls and nose columns. This multi-purpose, ultra-high, skyscraper was successfully completed in a record time by the joint venture of Samsung, BeSix and ArabTec sponsored by Emaar Properties.

**Keywords:** BurjKhalifa Tower, Quality, Construction, Formwork, Concrete.

\*\*\*

## 1. INTRODUCTION

The BurjKhalifa Tower is a multi-purpose, ultra-high, skyscraper was successfully completed in a record time by the joint venture of Samsung, BeSix and ArabTec sponsored by Emaar Properties. The tower has a total area of 479,830

m<sup>2</sup> that includes hotel, residential, commercial, shopping, entertainment, observatory, communication and parking facilities[10]. The figure 1 is a snapshot of the project summary.

Project Summary	
■ Project Brief	
<b>Project</b>	The Burj Tower (Main Contract BD-07)
<b>Construction Period</b>	47months ('05, 2.1 ~ '08, 12.30) Section A : '08, 3.15 (37.5 Month) Section B : '08, 12.30
<b>Contract Amount</b>	\$ 876,400,000 (\$1.5 Billion) JV Direct Cost : \$ 222,100,000 (25.3%) Provisional Sum : \$ 654,300,000 (74.7%)
<b>Client</b>	EMAAR Properties
<b>Consultant Group</b>	Architect : S. O. M. (Chicago) Project Management : Turner Construction Int'l Supervision Consultant : Hydar Consulting Quantity Surveyor : D.G. Jones
<b>Building Fact</b>	Floors : 169(189) floors / 3 Basement Floors Height : 705m (828 m - 830m TIP) Total : 479,830 m <sup>2</sup>
<b>Usage</b>	Hotel, Residence, Offices
Foundation: Mat 3.7m thick constructed over Piles: 1.5diameter 43m long; Pouring concrete in 4stages of 12000cum	





Fig- 1a: Snapshot of Project Summary – Burj Development, Project Brief





Fig- 1b: Snapshot of Project Summary – Building Usage, Mechanical




Fig- 1c: Snapshot of Project Summary – Electrical, Elevator & Escalator

### 1.1 Design Overview

The architectural design concept was derived from Blue Dick, the flower of the desert[8].

- The plan is reducing in a spiral pattern, symbolizing the Dubai economy.
- Seek the model of Future city for Middle East By the beauty of shape & scale

An effective, well-constructed and well-maintained building is essential for safety and durability of any structure. The tower has adopted the most stabilized Y-Shape, which provides stability by building weight shifts to end of the wings and structure considering both stability, constructability[9].




Fig- 2: Design Overview – Architectural and Structural




Fig- 3: Design Overview – Structural

Emergency evacuation is given prime importance during design development stage. The construction practices adopted at BurjKalifa Tower is simply “Do the right thing, right, first time, every time” by following established approved Project Quality Plan (PQP) and Inspection Test Plans (ITPs) with well narrated method statements and definite objective checklists/formats[3]. Project

Management Information System (PMIS) was effectively and efficiently used in day-to-day construction activities[2]. JV Operation Processed by Computer System and allows Information Real Time Update (Manager Group of JV Informed Instantly) and Ubiquitous Access (Site – EMO – Headquarter) to all stakeholders.




Fig- 4: Life boat evacuation and Stack effect

## 2. PROJECT QUALITY PLAN

Samsung JV considers the Project Quality Planning is a crucial step and it should be done well before construction work is due to commence[3,4]. It is amalgamated with the traditional project planning in such activities as nomination of subcontractors and suppliers, determination of

construction methods, construction programming, logistics plan, site layout, identification of manpower requirements and training needs, material and plant acquisition, etc. The following diagram depicts the development of the Project Quality Plan.




Fig-5: Project Quality Plan development and PMIS

Items	Contents
Manpower Management	- Management of 3,500 Workers Using RFID Card - Efficient Management of Direct-managed Works, Subdivision Analysis
Material Manage (Concrete)	- Concreting Live Update - Steel Rebar Bring In Managing
Drawing Management	- Database of Construction Drawing & Specification through intranet (Latest Version)
Documentation	- Instant communication (Live Search) - All Document in Soft Copy
Purchasing	- Purchase & Order, Bring In Managing By Computer
Sub-Con	- NSC Daily Report - Common Information and Communication
Etc.	- Internal Mail, Weather, Bulletin Board, Site Pictures, Telephone Directory, Etc.

### 2.1 Logistics Plan

The tower was located in the middle of Burj Dubai Development Site and there are favorable Access & Security (Air, Water, Road, Rail), mutual interface with other Burj Dubai project (Dubai Mall & Lake, Development Plan). The construction access is a crucial factor for safe and timely transport of material, equipment and manpower.

- Tower Section is enclosed by Podium

- Tower Section works, like stocking, lifting & concrete pumping, occur at the same time with Podium Works.
- Comparatively long distance from gate to Tower and disrupted by Podium construction.

It is necessary to provide sufficient well planned Stock Yards for the storage of material for project and limited Stock area for Tower Section. The tower site area is about 105,600m<sup>2</sup> and which includes the tower and podium. The podium is divided into zone –A Office Annex, Zone-B the Pool Annex and Zone-C the parking areas.

**Logistic Plan for Overall site**

- Scheme to Procure Stock Yard & Access
- To ensure stock yard & access, Podium Zone A, B & C structural work will be separated

**Work sequence in Podium Area**

- : Zone B -> A -> C (Tender : Zone A -> B -> C)
- : Partial site take-over, Drawing release schedule
- : Zone C will be used as a stock area & prefab yard until completion of Zone B

**Logistic Plan for Overall site**

- Stock Yards Procurement Scheme : Phase by phase

**Phase 1 (Zone B, Structural Works)**

- : Zone C - Main Stock Yard
- : Zone A - Stock yard & main T/C erection area
- (After completion of pile works)

**Phase 2 (Zone A, Structural Works)**

- : Zone B - Main pumping area & rebar prefab area
- : Zone C - Stock yard

**Phase 3 (Zone C, Structural Works)**

- : Zone A : Stock Yard
- : Start Zone C Inner Area after Completion of Zone A

Fig- 6: Logistics Plan for Overall site



Fig- 7: Logistics Plan for site for 37+ months and Plan for tower

2.2 Quality Control and Safety Plan

Quality Policy Statement is to ensure a totally Customer driven approach that meets and exceeds customer expectations through effective management and performance, good co-ordination increased productivity and greater focus on business objectives.

Quality Control Procedures will be developed in line with the project specification, ITP, approved relevant documents, submittals and approved method statements. All the

procedures will be developed and submitted formally to the consultant for approval and accordingly distributed to all concerned.

Repairs and Retrofitting if any should be carried with approved method statements and with approved materials[1, 5]

BurjKhalifa safety program has been developed considering 4 phases as illustrated below.



Fig- 8: Quality Control action Plan



Fig- 9: Safety Control Program and procedure



Fig- 10: Safety Control Program and procedure

2.3 Construction Equipment and Plan

The three tower crane were installed in tower Cores 1,2 and 3:




Fig- 11: Construction Equipment and plan





Fig- 12: Construction Equipment – Pumping Plan

3-day Cycle for walls and slabs have been adopted and sequencing of pouring concrete is shown below.







Fig-13: 3 day Cycle for Formwork and Rebar fabrication yard



Fig-14: Tower Slab Formwork and FRP shuttering

### High Strength Concrete

**Mix Design Summary & Application**

**Tower Concrete**

Items	Grade Of Concrete	Slump / Flow (mm)	Compressive Strength (lb)	E-Modulus (ksi)
Vertical Member	T-C80A-20	850 ± 75	80.0 (@56D)	43.8 (@90D)
	T-C80-14	600 ± 75	80.0 (@56D)	41.0 (@56D)
	T-C80-10	650 ± 50	80.0 (@56D)	41.0 (@56D)
Horizontal Member	T-C50-20	500 ± 75	50.0 (@28D)	-
	T-C50-14	600 ± 50	50.0 (@28D)	-

**Podium Concrete**

Grade of Concrete	Slump/Flow (mm)	Compressive Strength (lb)	Application
P-C60(P)	600-750	60.0 (@28D)	Piling
P-C50(O)	150 ± 25	50.0 (@28D)	Internal
P-C50(M)	150 ± 25	50.0 (@28D)	Mat. External
P-C35	125 ± 25	35.0 (@28D)	Blinding

### High Strength Concrete

**Concrete Mix Design & Testing**

**Mix Designs for High Strength Concrete**

- Satisfactory Mechanical Properties: Compressive Strength & E-Modulus
- Mass Concrete (Thick Section): Low Heat, HVFA Concrete
- Achievement of High Early Strength: 3-Day Cycle
- High-Pumpability Concrete: High Flowable Concrete

**Testing for the Applications**

- Creep & Shrinkage: Evaluation Creep & Shrinkage Coefficient
- Main Test (CTL, Chicago), Supplemental Test (Tech. Institute of Samsung)
- Pumping Simulation: max. 600m Horizontal
- Evaluate Concrete Properties & Pump Pressure
- Site Mock-Up Test: Ø2.1m Column & t:1.3m Wall (C80A)
- Evaluate Heat of Hydration, Curing, Overall Construction
- Pull-Out Test: Evaluate In-Situ Strength (Early Strength)
- Heat of Hydration Test & Analysis

Fig- 15: Concrete Mix design Summary and Testing

## 2.4 Concrete and Testing:

High performance concrete C60 and C80 grade concrete was used for vertical members, and C50 grade concrete was used for horizontal members.

### High Strength Concrete

**Concrete Quality Control**

**Curing Methods & Procedure**

- Proper Curing: Consider Construction Sequence
- Mass Concrete: Thermal Crack Control (Mock-Up Test)
- Tower: Vertical & Horizontal (Curing Compound)
- Podium: Vertical (Curing Compound), Horizontal (Water Ponding)

**Hot Weather Concreting**

- Control Concrete Temperature
- Chiller Plant & Ice, Shelter for Aggregate, etc.
- Normal Concrete: at Mixing 31°C
- Mass Concrete: at Mixing 28°C (≤1.5m), 25°C (>1.5m)
- Hot Weather Concreting
- Night Pour, Control the Concrete Delivery (interval)

**Quality Control for Concrete Supply**

- Monthly Test Report: Raw Material, Cube Strength, etc.
- Quality Control Procedure at Plant: Batching variation




Fig-17: High Strength concrete Quality Control Testing and Pouring






Fig- 18: High Strength concrete Testing Register and Strength Profile of Tower C80 Concrete

2.5 Spire Erection Plan




Fig- 19: Spire Installation sequence

2.6 Building Movement Monitoring System




Fig- 20: Building Movement monitoring and Checking Verticality of Tower walls

### 3. CONSTRUCTION PHOTOGRAPHS



Fig- 21: Auto Climbing Formwork



Fig- 22: Rebar: Mat Foundation and Tower Slab



Fig- 23: QC Inspection: Mat Foundation and Tower Beam



**Fig- 24:** Safety is a must for every one- PPEs and Safety induction to Visitors

#### 4. CONCLUSION

The successful completion of the BurjKhalifa tower is mainly attributed to the adoption of latest construction technology, construction materials and Auto-climbing formwork in addition to the excellent Project Quality Plan, which encompasses Logistics plan, Equipment Plan, Spire Erection plan and consistently adhering to Inspection Test plans for materials, equipment, and work inspections. The BurjKhalifa Tower becomes an objective evidence of 'Quality Icon', which demonstrates the construction of an Ultra High skyscraper which meets all the technological and constructional challenges and stands as a benchmark for future construction of super ultra-high skyscrapers.

#### ACKNOWLEDGEMENT

The author is highly indebted to the Managing Director, Management consultant and VCEOs of Azmeel Contracting Company, Saudi Arabia, for their continuous support while preparing this paper. The author also extends many thanks to BurjKhalifa Tower friends and especially to Samsung JV Management.

#### REFERENCES

- [1] Rajendra Prasad D.S., Method statement for Retrofitting of Tower slabs, Rev. 2, Samsung JV, Dubai, 2006
- [2] Rajendra Prasad D.S., Project Management -A Simple Approach, Sapna Book House, Bangalore, 2011
- [3] Rajendra Prasad D.S., Quality Management System-A Simple Approach, Sapna Book House, Bangalore, 2003, 2011
- [4] Rajendra Prasad D.S., ISO 9001:2015 Quality Management Systems – Implementation, Sapna Book House, Bangalore, 2015
- [5] Rajendra Prasad D.S, Structural Evaluation of various methods of retrofitting of Tower slabs, National Conference on Recent Trends in Civil Engineering, JSSIT, Bangalore, 2015

- [6] Rajendra Prasad D.S, Kiran Kumar H R, Dattatreya J K, Development of design software for the analysis of Tall Chimney, ICCIT, Mysore, June 2012.
- [7] Rajendra Prasad D.S, Swaroop N , Dattatreya J K, Naveena.P.C , Selection of Pile Foundation Using Expert System and Design Using Visual Basic Programme For High Rise Building, International Engineering Post Graduate Research Conference ENGGPOS 2013 Technical program -2013, Feb 1-2, 2013, Coimbatore.
- [8] Abdelrazaq, A, Kim, K. J., Kim, J.H. "Brief on the Construction Planning of the Burj Dubai Project, Dubai, UAE", 17th IABSE Congress, Creating and Renewing Urban Structures – Tall Buildings, Bridges and Infrastructure, Chicago, September 17-19, 2008.
- [9] Baker W, Pawlikowski J. Higher and higher: the evolution of the buttressed core. Civil Eng. 2012; 82(10): 58–65.
- [10] Council on Tall Buildings and Urban Habitat. Tall Building Database. ctbuh.org.

#### BIOGRAPHIES



Dr. Rajendra Prasad D S is a Quality Head at Azmeel Contracting Company, one of the largest construction company in the Kingdom of Saudi Arabia, that caters to Buildings, Infrastructures, Industrial and Refinery structures. Previously, Dr. Rajendra Prasad worked as a Chief Engineer-Quality in BurjKhalifa Tower Project, Dubai with Samsung JV. He is a postgraduate in Civil engineering from UVCE, Bangalore and having a Post-Doctoral degree in Civil Engineering. He is an author of more than 48 research papers and 21 books in various disciplines.